



Project: First Stage of SCADA/COMMUNICATION

Customer: ABB AB Network Management (Sweden)

Years: 2008-2011

Performed works:

- Removal of debris (of old equipment), clearing position for the new equipment
- Digging of cable routes in outdoor switchyards
- Erection of cubicles including preparatory civil works
- Installation of cubicle support bars, cable trenches and cable ladders
- Earthing of cubicles and wall mounted panels
- Installation of cables between RTUs and plant sources, between AC/DC distribution and RTUs and between RTUs and Telecom cabinets
- Fitting of glands for a/m cables
- Termination, applying ferrules/lugs of cables and wires
- Installation of transducers and auxiliary relays (in plant cubicles) as applicable
- Termination and testing of modified circuits in plant
- Wiring check of all installed cables/wiring (continuity test)
- Testing of new and existing equipment such as transducers, command interposing relays, indication and alarm relays
- Installation of RTU, battery, battery charges and generators
- Testing of each signal from plant source up to terminals in the SCADA equipment
- Red-marking of installation/commissioning drawings

Project: First Stage of SCADA/COMMUNICATION

Customer: ELTEL Networks Oy (Finland)

Years: 2008-2011

Performed works:

- Installation of cables (including fixing)
- Installation of OPAC cable in the pipe
- Works for DPLC (Hrazdan HPP - Sevan HPP)
- Works for the existing DPLC (SS Agarak - SS Shinuair)
- Works for the existing DPLC (Spandaryan HPP - Shamb HPP)
- Digging and preparation of the trench for the OPAC cable
- Civil works for DPLC
- Manufacturing and installation of foundations



Project: UNIT N5 of Hrazdan TPP

Customer: JSC “Interautomatika” (Russian Federation)

Years: 2010-2011

Performed works:

- Installation of control, measurement and automation equipment of main building, Heller tower, cost pump station, gas regulatory and gas preparatory buildings, chimney, pressurized air compressor building
- Installation of power supply panels and UPS equipment of technical programming complex
- Installation of controller cubicles, communication devices, intermediary terminals, intermediary relays, secondary converters of mechanical quantities and vibrations, over speeding protection
- Installation of network equipment panels
- Installation of control panels
- Installation of technical programming complex components on the unit control panel, including installation of the common usage screens
- Installation and connection of power supply cables of technical programming complex
- Installation and connection of network cables
- Installation of power unit simulator equipment
- Installation of the communication systems with the local control systems (gas turbine, gas pressurizing station, erection system and synchronization of the steam turbine generator, switchyard 220 kV, water heating boiler)

Project: Repair works on 220 kV SS “Kamo”

Customer: CJSC “High voltage electrical networks of Armenia”

Year: 2011

Performed works:

- Installation of 35 kV cable end-muff



Project: Pump Station “Artashar”

Customer: Armenian Branch of SADE (France)

Year: 2011

Performed works:

- Delivery and installation of the power supply panels
- Delivery and installation of the power cables
- Installation of the earthing system
- Installation of the current protection system in the main pump power panel
- Installation of the external lighting system of the pump station
- Complex commissioning of the installed equipment

Project: Installation works at branch” South”

Customer: JSC “Electrical Networks of Armenia”

Year: 2011

Performed works:

- Removal of 6 kV power panels
- Removal of 10 kV power panels
- Installation of 6 and 10 kV power cells
- Civil construction works
- Installation of the power cables
- Commissioning of the installed equipment